BRUHATH BANGALORE MAHANAGARA PALIKE

Yelahanka Zone, Kodigehalli Sub Division

DETAILED ESTIMATE FOR **Pothole filling in Devinagara, Lottegollahalli and surrounding area in ward no. 08, kodigehalli**

Est. Cost Rs. : 500000.00

Sl. No.	Description	Unit	Dimensions				Qty.	Rate (Rs.)	Amount (Rs.)
			No.	L	B	D			
1	KSRRB 300-45. Scarifying stone metal crust 50 to 100 mmthick with pick azxes along with premix carpet / surface dressing and stacking of old serviceable materials by manual means including cost of all labour charges complete as per specification. (Page No. 146, Item No. 19.51, PWD SR 2018-19)								
	Devinagara main roads	sqm	20	3.20	2.20		140.80		
	Devinagara cross roads	sqm	15	3.30	2.00		99.00		
	Lottegollahalli main roads	sqm	18	2.90	1.80		93.96		
	Lottegollahalli cross roads	sqm	26	2.80	2.60		189.28		
		sqm					523.04	84.80	44354.00
	Basic Rate	80.00							
	Area Weightage @ 6%	4.80							
	Total	84.80							
2	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per MORTH specification No. 406, Page No. 155 / Item No. 20.18 / PWD SR 2018-19								
	Devinagara main roads	Cum	20	3.20	2.20	0.20	28.16		
	Devinagara cross roads	Cum	15	3.30	2.00	0.20	19.80		
	Lottegollahalli main roads	Cum	18	2.90	1.80	0.20	18.79		
	Lottegollahalli cross roads	Cum	26	2.80	2.60	0.20	37.86		
							104.61	2001.28	209350.00
	Basic Rate	1888.00							
	Area Weightage @ 6%	113.28							
	Total	2001.28							
3	KSRRB 3000: Filling Pot-holes and patch repairs with bituminous concrete, 40 mm, KSRRB M3000-5, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3 back filling the pot hole with bituminous material as per clause 500.4 compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications, MORTH specification No. 3004.2, P. No. 259 / Item No. 35.5 PWD SR 2018-19								
	Devinagara main roads	Sqm	20	3.20	2.20		140.80		
	Devinagara cross roads	Sqm	15	3.30	2.00		99.00		
	Lottegollahalli main roads	Sqm	18	2.90	1.80		93.96		

Sl. No.	Description	Unit	Dimensions				Qty.	Rate (Rs.)	Amount (Rs.)
			No.	L	B	D			
	Lottegollahalli cross roads	Sqm	26	2.80	2.60		189.28		
							523.04	365.70	191276.00
	Basic Rate	345.00							
	Area Weightage @ 6%	20.70							
	Total	365.70							
4	Sub-Total								444980.00
5	Add GST charges at 12%						12.00		53398.00
6	Miscellaneous & Rounding off							L/S	1622.00
	Total Rs								500000.00

(RupeesFive Lakhs only)

CERTIFICATE:

1 The work spot has been inspected and the work is found necessary.
2 This estimate is prepared as per P.W.D S.R of 2018-19
3 The provisions were made in this estimate are necessary and adequate.
4 This works come under B.B.M.P. limits.
5 This work has not been taken previously under any other grant.

Assistant Engineer
Ward no. 08
Kodigehalli

Assistant Executive Engineer
Kodigehalli Sub Division
BBMP

Executive Engineer
Byatrayanapura Division
BBMP

ADMINISTRATIVE APPROVAL
Accorded For Rs. 5.00 Lakhs
Head of A/c. P1771
Div. Ref. No. 41/19-20 Date 25/7/19
AE 25/07
EE(BTP) 25/07

TECHNICAL SANCTION
Accorded For Rs. 5.00 Lakhs
Head of A/c. P1771
Div. Ref. No. 65/19-20 Date 25/7/19
AE 25/07
EE(BTP) 25/07